
Filler blocks
6x12 Panel P6
4x10 Panel P16
Panel pt. 5 - 6x8 dapped at ends
Panel pt. 17 - 4x12
Panel P5 - 4x10
Panel P17 - 4x8
Dapped at ends to frame between diags.
Alternate A - 4"ø S.R. with 7/8" Bolts
Alternate B - 4"ø S.R. with 3/4" Bolts
Plus extra Bolts as shown

PANEL POINT 2

PANEL POINT 3
PANEL POINT-15-SIMILAR

PANEL POINT 4
PANEL POINT-14-SIMILAR

PANEL POINT 5
PANEL POINT-17-SIMILAR

PANEL POINT 6
Alternate - Bapisco Split Rings with Shear Plates

PANEL POINT 8
PANEL POINT 10-SIMILAR

PANEL POINT 9

PANEL POINT 18

PANEL POINT b

PANEL POINT c

PANEL POINT d
PANEL POINT p-SIMILAR

PANEL POINT e

PANEL POINT q
PANEL POINT-16K-SIMILAR

PANEL POINT h
PANEL POINT-f-SIMILAR

PANEL POINT j
PANEL POINT-r-SIMILAR

PANEL POINT Q
PANEL POINT-g-SIMILAR

PANEL POINT s

NOTE:
Minimum edge distance of 2⅛" is to be maintained for all members.

3/16/43 Panel Points G, H, g & a - Alternates.

APPROVED BY BUREAU OF AERONAUTICS

DATE

NAVY DEPARTMENT — BUREAU OF YARDS & DOCKS

NAVAL AIR STATION
TILLAMOOK, ORE.
LIGHTER-THAN-AIR HANGAR
ROOF TRUSS-- PANEL POINT DETAILS
HANGAR - OCEAN

Approved Aug. 16, 1942 — Y. & D. Drawing No. 212850

For Chief of Bureau

Prepared by F.E.H.
Traced by G.B.
Checked by H.W.H.
Detailed by L.E.B.
Group Checker
Chief Draftsman
Asst. Engr. 4-1-43
Proj. Mgrs.
Design Mgr.
Sheet ... of ... sheets
Applying contract No. 5424

ELIZABETH CITY, N.C. Sheet 2 of 5 — Index Sheet — Proj. 18537
ELIZABETH CITY, N.C. Sheet ... of ... accompanying contract — Proj. 4906
LAKEHURST, N.J. Sheet ... accompanying contract — Proj. 4853

1335-45-5

5/16

Binding

315

POOR COPY